



# आत्मा राम सनातन धर्म महाविद्यालय ATMA RAM SANATAN DHARMA COLLEGE



ACCREDITED GRADE 'A' BY NAAC  
All India 14th Rank By NIRF (MHRD)

(दिल्ली विश्वविद्यालय) (University Of Delhi)

धौलाकुआँ, नई दिल्ली-110021 DHAULA KUAN, NEW DELHI - 110021

फोन / Phone : (+91) (11) 24113436, 24117508 फैक्स / Fax : (+91) (11) 24111390

web : www.arsdcollege.ac.in

संदर्भ सं / Ref. No. ARSD/Misc/CW/19


दिनांक / Date 26/11/19

## Short Term Tender Notice

Sealed Tenders/quotation are invited from Reputed, Qualified & Experienced registered firms for the Award of Miscellaneous Civil Works in the College premises as per (Annexure -A) on the following terms and conditions: -

- 1 The Tender/quotation must be accompanied by a bank draft of **Rs. 5,000/-** as Earnest Money Deposit (EMD) in favour of "**Principal, ARSD College**", payable at **New Delhi**.
- 2 The Successful bidder will be required to submit Performance Guarantee of 5%
- 3 The site can be inspected by contacting Mr. Vijender (Assistant) in the College office (Monday to Friday).

Your Tender/quotation complete in all respects on your **firm's letter head** and enclosed in a sealed envelope superscribed "**Tender/Quotation for Miscellaneous Civil Work in the College premises**" and addressed to **Principal, Atma Ram Sanatan Dharma College, (University of Delhi), Dhaula Kuan, New Delhi – 110021**, must reach to the College latest by **09.12.2019 (Monday) (3:00 PM)**.

  
Principal 26/11/19

Annexure -AATMA RAM SANATAN DHARAM COLLEGE, DHAULA KUAN, NEW DELHIMISCELLANEOUS CIVIL WORKS IN COLLEGE PREMISES

**Repair and renovation of cultural Room, Ventilation of Atrium, Renovation of open area outside in shed near canteen and computer laboratory and rain water drainage system in New Girls Common Room (GCR)**

S. No.	Description	Unit	Qty.	Rate (Rs.)	Amt. (Rs.)
1.	Dismantling of CC Floor for making proper bed for fixing of floor tiles and disposal of malba as per instruction of Engineer in-charge	Sqm.	15		
2.	Brick work with common burnt clay FPS (Non-Modular) Bricks of Class designation 7.5 in super structure in cement mortar 1:6	Cum.	10		
3.	12mm cement plaster in fine sand of mix 1:4	Sqm.	60		
4.	Providing and fixing ceramic wall tiles of required sizes and pattern complete with filling of pigments etc.	Sqm.	50		
5.	Providing and fixing vitrified floor tiles of size 600 x 600mm with all necessary pigments and thick cement base	Sqm.	20		
6.	Reinforced cement concrete work in slabs having slope upto 15 degree including all cost of MMS bars (reinforcement) 10mm, with centering shuttering and finishing etc. complete in CCM-20	Cum.	5		
7.	Providing and fixing MS steel work welded in built-up section / framed work including cutting, hoisting and fixing in position as required in section MS Angle 35 x 35 x 5mm duly fixed with pre-fabricated MS Jali of 10 SWG, fixing over walls and applying a priming coat of approved steel primer.	Sqm.	15		
8.	Providing and fixing ISI marked flush door shutters conforming to IS:2202 including lamination with 1mm thick mica sheet both side of the shutter including all fittings and fixtures, wooden margins etc. complete.	Sqm.	5		
9.	Providing and fixing RCC Kitchen Sink of Size 1200 x 600mm (inner side) with all reinforcement, centering, shuttering, water inlet and outlet system and all sanitary installations etc. clad with vitrified tiles or granite stone.	Job	1		
10.	P/F 150mm dia PVC pipe for making rain water drainage system connecting to main pipe of 100mm dia through PVC Tee, Elbows, End Caps and all other required accessories i.e. MS Clamps for fixing over walls and any other surface.	Rmt.	50		





**ATMA RAM SANATAN DHARAM COLLEGE, DHAULA KUAN, NEW DELHI****MISCELLANEOUS CIVIL WORKS IN COLLEGE PREMISES**

**Repair and renovation of cultural Room, Ventilation of Atrium, Renovation of open area outside in shed near canteen and computer laboratory and rain water drainage system in New Girls Common Room (GCR)**

11.	Supplying and fixing stainless steel turbo exhaust fan of size 600mm dia with polycarbonated sheet frame base including fixing with all nut and bolts and other accessories including M.S frame base of Angle frame 40x40x6 mm	Nos.	6		
12.	Painting of walls and ceiling with premium acrylic emulsion paint (plastic paint) including with wall care putty coat with all material and labour etc. complete.				
	a) Ceiling	Sqm.	20		
	b) Walls	Sqm.	20		
13.	Painting of MS structure with synthetic enamel paint of branded companies in required shade as per approval of engineer-in-charge.	Sqm.	50		
14.	P/F Electrical Wiring concealed or batton wiring over walls and filling using copper wire in appropriate size with all switches, sockets, MS boxes but without accessories.				
	a) Light points	Nos.	10		
	b) Power Points	Nos.	5		

